BARMARYEE ROAD
CONDON DRIVE
ROCKHAMPTON ROAD
OCEAN PARK AVENUE
ACCESS 1
ACCESS 2
ACCESS 3
ACCESS 4
ACCESS 5
ST 1
ST 2
ST 3
PSM 182212

STATION TABLE

STATION	EASTING	NORTHING	R.L.	DESCRIPTION	POINT No.
PSM 104199	267012.458	7438556.027	59.989	Permanent Mark	104199
PSM 182212	267200.250	7439707.987	52.684	Permanent Mark	182212
ST 1	267142.986	7439688.995	52.585	Screw in Telstra MH	10001
ST 2	267240.040	7439790.862	49.991	Screw in Kerb	10002
ST 3	267181.947	7439615.597	52.968	Screw in Path	10003

NOTES
1. Refer Sheets G-02 to G-04 for Typical Sections.

LEGEND

- Proposed 50mm Asphalt Surfacing
- Proposed 100mm Concrete Path
- Proposed Kerb & Channel
- Proposed Road Signs
- Proposed Light Pole & Conduit
- Proposed 2x 400mm Turf min.
- Proposed Landscaping
- Proposed Water main (W150)
- Proposed Irrigation Service Connection (W63)
- Proposed Drainage RCP

All existing services shown greyed.

FOR CONSTRUCTION
06/11/2018

Surveyed: K.B.L.		AMENDMENTS DESCRIPTION	APPR'D	DATE	
Date: Dec. '17					
Ref Mark: 104199 | R.L. 59.989					
Datum: Horiz. GDA94 Vert. AHD					
Zone: 56					
Survey Book: 159	B	Revised Water, Signals, Stormwater, Ocean Park Ave			
Ancillary Project: 16-134	A	Original Issue	T.L.	3.5.18	

0 2,5 5 7,5 10 PLAN & HORIZ. 1:500
SCALES m. FULL SIZE A3

Livingstone SHIRE COUNCIL

Designed	K.B.L.	06/11/18
Checked		7.11.18
Endorsed		8.11.18
Recomm.		8.11.18

APPROVED P.J. McKone
RPEQ No 27245 DATE 9/11/18
for COORDINATOR CIVIL DESIGN

ROCKHAMPTON RD, BARMARYEE ROAD, CONDON DR, OCEAN PARK AV, YEPPOON
INTERSECTION UPGRADE - GENERAL
OVERALL LAYOUT

Dwg No. 11-148-G-01
Sheet No. 1 of 78
Job No: C.0966564
A B

O:\Infrastructure\Projects\2011 (RRC)\148 - Barmaryee Rd Rbout\3. Design\ACAD Dwgs\(2) Intermediate\Plans\General.dwg, G1, 06/11/2018 5:47:33 PM, 1:1